

## PCC Pavement

- Forms set 35
- Concrete in place 90
- Forms removed and testing complete 98
- Substantially complete including cleanup 100

## Concrete Structures

- Falsework erected 10
- Forming complete 20
- Concrete in place 80
- Forms removed 90
- Concrete tested and finished 98
- Substantially complete including cleanup 100

## Steel Structures

- Falsework erected 10
- Steel in place 80
- Bolting and welding complete 90
- Painting complete 98
- Substantially complete including cleanup 100

## Notes:

- (1) These percentages are typical. They may be adjusted based on a detailed analysis of circumstances on given project.
- (2) Whenever partially complete work entails continuing maintenance, an appropriate percentage should be retained to cover those costs.