

Western Federal Lands Highway Division

PETTY CREEK ROAD NEWSLETTER

Mike Hurst, Project Engineer
michael.hurst@dot.gov
PO Box 1015
Frenchtown, MT 59834
406-626-0006

Project Description

Petty Creek road is located near Alberton, MT south of exit 77 on I-90. The project begins after crossing the railroad tracks near the Clark Fork River and extends for 11.7 miles south into Lolo National Forest. Project improvements will include paving the first 9.8 miles to a consistent 24' width, replacing the Petty Creek Bridge at MP 9.7, improving roadway alignment and improving drainage. Missoula County will assume maintenance duties upon completion of the project.



Road Surface conditions

The current road surface is existing compacted gravel with large areas of newly constructed fill. All areas actively worked will be shaped at the end of each day's operations to a tight passable surface. Isolated soft spots and rough areas may still exist, please use caution.



Current and Upcoming Work

The contractor, West Co., is currently installing aquatic passage culverts at isolated areas throughout the project. These culverts must be installed prior to September 15 due to environmental restrictions. Dirtwork operations will begin again in early September.



Traffic Delays

Please expect 15-30 minute delays, Monday through Saturday, 7am to 6pm. The South Fork Road will be closed Aug 23 to Aug 31. Please use caution when passing laborers and machines working in the road and on the shoulder. There may be one-lane roadway left overnight, controlled with either temporary stop lights or "Stop and proceed when clear" signage.



The Storm Water Pollution Prevention Plan (SWPPP) for this project is available for viewing at the Office of the Project Engineer, located at 16862 Beckwith St, Suite N in Frenchtown.





**Above - 12'x7' concrete box culvert installation at West Fork of Petty Creek.
Below - Streambed infill of concrete box culvert at Madison Gulch.**

